1 A3.0 WEST ELEVATION (COON RAPIDS ROAD)
1/4" = 1'-0"

2 A3.0 SOUTH ELEVATION
1/4" = 1'-0"

3 A3.0 NORTH ELEVATION (EGRET BLVD)
1/4" = 1'-0"

4 A3.0 EAST ELEVATION
1/4" = 1'-0"

ELEVATION KEYNOTES:

1. EIFS, SYSTEM – DRYVIT OUT DESIGN; OR APPROVED EQUAL COLOR – #381 MONASTERY BROWN, FINISH – SANDPEBBLE
2. PRE-FINISHED METAL GUTTER AND DOWN SPOUT SYSTEM, COLOR – DARK BRONZE
3. INSULATED METAL PANEL, COLOR – TO MATCH DOOR FRAME SYSTEM(DARK BRONZE)
4. ALUMINUM STOREFRONT WINDOW & DOOR SYSTEM
5. STANDING SEAM METAL ROOF SYSTEM, COLOR – DARK BRONZE
6. CONCRETE FIELD BRICK, SPEC-BRIK OR APPROVED EQUAL, 4X16, COLOR – #921 FIRE BRICK RED
7. CONCRETE ACCENT BRICK, SPEC-BRIK OR APPROVED EQUAL, 4X16, COLOR – #311 GOLDLEAF
8. CONCRETE "SOLDIER COURSE" BRICK, SPEC-BRIK OR APPROVED EQUAL, 8X16, 3 SCORE RAKE, COLOR – #921 FIRE BRICK RED
9. CONCRETE ACCENT BRICK, SPEC-BRIK OR APPROVED EQUAL, 8X16, 1 SCORE RAKE, COLOR – #311 GOLDLEAF, FILL SCORES WITH GROUT.
10. HARDI-PLANK ACCENT TO MATCH CONCRETE ACCENT SPEC-BRICK OR APPROVED EQUAL COLOR – #311 GOLDLEAF
11. HOLLOW METAL DOOR AND FRAME SYSTEM. COLOR – PAINT TO MATCH (6)
12. PRE-FINISHED METAL FASCIA & TRIM, COLOR – DARK BRONZE
13. CONTRASTING DIE CUT VINYL 8" HIGH NUMBERS. VERIFY ADDRESS NUMBER
14. RIDGE VENT SYSTEM, PROVIDE CODE REQUIRED VENTING
15. ADDITIONAL VENTING AREAS, IF RIDGE VENT SYSTEM DOES NO PROVIDE CODE ADEQUATE VENTING
16. 16" x 16" PRE-FINISHED INTAKE AIR GRILLE, COLOR– DARK BRONZE (COORDINATE SIZE AND LOCATION WITH HVAC PLANS)
17. COILED CARWASH DOOR (SEE FINAL APPROVED CARWASH PLANS)
18. 6" HORSE SHOE STEEL BOLLARD
19. PUMP NUMBER SIGNAGE
20. CANOPY RAIN LEADER, INSTALLED WITHIN CMU CANOPY COLUMN, DAYLIGHT AT BASE OF COLUMN
21. ACCESS PANEL, TYPICAL AT ALL CANOPY COLUMNS, COORDINATE WITH ELECTRICAL PLANS, PAINT TO MATCH COLUMN
22. SINGLE BUCKET SERVICE CENTER. SEE EQUIPMENT SCHEDULE (B7)
23. ALUM. WINDOW SYSTEM
24. TRASH ENCLOSURE GATE SYSTEM
25. GAS DISPENSING SYSTEM (SEE GAS DISPENSING PLANS)
26. CANOPY SINGAGE, SEE SIGNAGE PLANS
27. GAS ISLAND CANOPY, SEE GAS ISLAND CANOPY PLANS FOR FURTHER INFORMATION
28. 24" X 20" X 6" PRECAST PIER CAP, SLOPE TO SHED WATER
29. DIE CUT SOLID VINYL 12" HIGH X 1" THICK NUMBERS. COLOR–DARK BRONZE, VERIFY ADDRESS NUMBER

CONSULTANT:

NORR

SEAL:

THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION PURPOSES UNTIL THE SEAL AND SIGNATURE OF THE RESPONSIBLE REGISTRANT APPEARS ON THE DRAWING, AND PROPER PERMIT FORMS AND RELATED FEES ARE TRANSMITTED BY THE OWNER, OWNER'S AGENT OR CONTRACTOR TO THE AUTHORITY HAVING JURISDICTION.

DATE	ISSUED FOR	REV
07.10.2015	FOR REVIEW	

Project Manager	Drawn
Project Leader	Checked
Date	Dept Mgr Approval

Client
C-Store Partners, LLC

Project
PROPOSED NEW BUILDING COON RAPIDS, MN

Drawing Title
EXTERIOR COLOR ELEVATIONS

DO NOT SCALE DRAWING

Project No.	Drawing No.
	A3-01